


Draft UN GTR on in-vehicle battery durability for electrified vehicles, applicability



*- other qualifications than GVWR, or maximum laden, mass apply

1998 Agreement Vehicle Classification

(1958 classifications not addressed in the draft GTR)

“This UN GTR applies to PEV and OVC-HEV vehicles of categories 1-2 and 2, both having a technically permissible maximum laden mass not exceeding 3,500 kg, and to all vehicles of category 1-1”

- "Category 1 vehicle" means a power driven vehicle with four or more wheels designed and constructed primarily for the carriage of (a) person(s).
- “Category 1-1 vehicle" means a category 1 vehicle comprising not more than eight seating positions in addition to the driver’s seating position. A category 1-1 vehicle cannot have standing passengers
- "Category 1-2 vehicle" means a category 1 vehicle designed for the carriage of more than eight passengers, whether seated or standing, in addition to the driver and having a maximum mass not exceeding 5 tonnes
- "Category 2 vehicle" means a power driven vehicle with four or more wheels designed and constructed primarily for the carriage of goods

EPA Vehicle Classification

40 CFR §86.1803-01

Gross vehicle weight rating (GVWR) means the value specified by the manufacturer as the maximum design loaded weight of a single vehicle, consistent with good engineering judgment.

LDV/T means light-duty vehicles and light-duty trucks collectively, without regard to category.

Light-duty vehicle means a passenger car or passenger car derivative capable of seating 12 passengers or less

Light-duty truck means any motor vehicle rated at 8,500 pounds GVWR or less which has a curb weight of 6,000 pounds or less and which has a basic vehicle frontal area of 45 square feet or less, which is:

- (1) Designed primarily for purposes of transportation of property or is a derivation of such a vehicle; or
- (2) Designed primarily for transportation of persons and has a capacity of more than 12 persons; or
- (3) Available with special features enabling off-street or off-highway operation and use.

Medium-duty passenger vehicle (MDPV) means any heavy-duty vehicle (as defined in this subpart) with a gross vehicle weight rating (GVWR) of less than 10,000 pounds that is designed primarily for the transportation of persons. The MDPV definition does not include any vehicle which:

- (1) Is an "incomplete truck" as defined in this subpart; or
- (2) Has a seating capacity of more than 12 persons; or
- (3) Is designed for more than 9 persons in seating rearward of the driver's seat; or
- (4) Is equipped with an open cargo area (for example, a pick-up truck box or bed) of 72.0 inches in interior length or more. A covered box not readily accessible from the passenger compartment will be considered an open cargo area for purposes of this definition.

Heavy-duty vehicle means any motor vehicle rated at more than 8,500 pounds GVWR or that has a vehicle curb weight of more than 6,000 pounds or that has a basic vehicle frontal area in excess of 45 square feet. Note that MDPVs are heavy-duty vehicles that are in many cases subject to requirements that apply for light-duty trucks