# The proposal for GTR 21 revision in the next phase

2024.09

Prepared by China


# K1 measurement for oil-cooled highly integrated electric drive system

2024.09

### 1. Introduction

- One prototype highly-integrated oil-cooled Electric Drive System has been adopted to investigate the validity of direct measurement of K1 value.
- As can be seen in the schematics of the oil passage, oil flows between the electric motor and the speed reducer, which increases the difficulty of direct measurement.


Test EDS



### Schematics of cooling system

Coolant passage


Oil passage




# 2. Experimental Approach

• The EDS has been placed inside a mini climate chamber and the oil passage between the motor and the speed reducer has been blocked (oil circulated inside the motor to cool the stator and the rotor).

Test System



#### Schematics of the Test System



## 3. Results Comparison

- Steady state running conditions have been repeated to obtain the K1 value, shown in the table below, which confirms the validity of direct measurement of the K1 value for oil-cooled highly integrated electric drive systems.
- Future work needed: 1) more validation data, 2) comparison with on-board data, 3) possibility of the calculation of K2.

| Test No. | Speed (rpm) | Torque (Nm) | Voltage (V) | Current (A) | K1 (Efficiency) |
|----------|-------------|-------------|-------------|-------------|-----------------|
| 1        | 3509        | 36.894      | 300         | 0.491       | 92.03%          |
| 2        | 6514        | 73.789      | 300         | 1.795       | 93.46%          |
| 3        | 7014        | 110.684     | 300         | 2.884       | 93.96%          |
| 4        | 6014        | 147.579     | 300         | 3.351       | 92.45%          |
| 5        | 6514        | 184.475     | 300         | 4.556       | 92.06%          |


# Experimental validation of TP1 test on a fuel cell vehicle

2024.09

# 1. Introduction

- One fuel-cell based sedan has been selected to carry out validation of TP1 test procedure,
- The specification of the FCV is shown in table below.

FCV on chassis dynamometer





### **FCV specification**

| Length (m)                            | Width (m)       | Height (m)                       | Curb weight (kg) |  |  |  |
|---------------------------------------|-----------------|----------------------------------|------------------|--|--|--|
| 4.82                                  | 1.89            | 1.48                             | 1900             |  |  |  |
| Fuel cell pow                         | er rating (kw)  | Fuel cell maximum efficiency (%) |                  |  |  |  |
| 67                                    | 7.5             | 62                               |                  |  |  |  |
| Fuel cell power                       | r density (W/L) | Fuel cell power density (w/kg)   |                  |  |  |  |
| 58                                    | 3.3             | 625                              |                  |  |  |  |
| Fuel cell du                          | ırability (h)   | Fuel cell Protection degree      |                  |  |  |  |
| > 10000 (atter                        | nuation < 10%)  | IP67                             |                  |  |  |  |
| Fuel cell cold-start temperature (°C) |                 |                                  |                  |  |  |  |
| ≤-30                                  |                 |                                  |                  |  |  |  |

# 2. Speed of maximum power


• The maximum power 97.5W appears when the speed is 67kph, which shows good agreement with vehicle acceleration results.





### 3. Results

- The inferred maximum power is 97.81kW while the sustained power is 96.81kW.
- The deviations of four repeats are below 5%.



#### Experimental data

|                        | 2 <sup>nd</sup><br>Repetition | 3 <sup>nd</sup><br>Repetition | 4 <sup>nd</sup><br>Repetition | 5 <sup>nd</sup><br>Repetition |
|------------------------|-------------------------------|-------------------------------|-------------------------------|-------------------------------|
|                        | •                             | •                             | •                             | •                             |
| U <sub>REESS</sub> (V) | 312.35                        | 313.78                        | 312.47                        | 313.0                         |
| I <sub>REESS</sub> (A) | 264.99                        | 257.47                        | 255.52                        | 250.03                        |
| U <sub>Fccu</sub> (V)  | 312.35                        | 313.78                        | 312.47                        | 313.0                         |
| I <sub>Fccu</sub> (A)  | 85.66                         | 84.42                         | 85.99                         | 82.96                         |
| P <sub>DCDC</sub> (kw) | 0.66                          | 0.82                          | 0.81                          | 0.81                          |
| P <sub>aux</sub> (kw)  | 0.51                          | 0.56                          | 0.65                          | 0.65                          |
| K1 (Efficiency)        | 0.9217                        | 0.9228                        | 0.9226                        | 0.9218                        |
| Speed (kph)            | 67                            | 67                            | 67                            | 67                            |

Note: the electric drive system is water cooled and K1 directly measured