

Progress update on the EU MAC Pilot Programme


Informal meeting of MACTP working group at 65th GRPE

GRPE document number: GRPE-IG-MACTP-05-02

January 15th 2013
Geneva

By the Consortium of:


TUG: Stefan Hausberger
LAT: Savas Geivanidis, Zissis Samaras
TNO: Willar Vonk, Robin Vermeulen




Assigned by: EC DG Enterprise Nikolaus Steininger under specific contract SI600239 implementing Framework contract ENTR/F1/2009/030.1

Contents:

- › Introduction
- › Progress MAC Pilot Programme
- › Current status of the procedure
- › Open issues
- › Outlook





Targets of the MAC Pilot Programme


→ Finalization of the draft procedure, evaluation of the procedure and drafting a technical annex to the Regulation

A draft type approval test procedure for MAC “energy efficiency” was already developed by the Consortium of TUG, LAT, KTI and TNO.


A Pilot Programme is defined to:

- › Cover open issues and options for settings and data processing
- › Evaluate the test procedure (Round Robin)
- › Finalize the MAC test procedure and draft a technical annex to the Regulation

During Pilot Phase, labs also gain further experience with the procedure





MAC Pilot Test Programme contains two test phases:



A bird's-eye view of the MAC test procedure (1/2)

(Status 15 January 2013)

- › Emission test of the complete system of vehicle + MAC
- › To be performed in an emission laboratory
- › Driving the test vehicle on a chassis dynamometer
- › Driving a driving cycle, preceded by a soak phase. The cycle has a phase for:
 - › Conditioning/ stabilization of the cabin temperature
 - › Three steady state situations with MAC on (idle, 50, 100km/h)
 - › The same three steady state situations with MAC off
- › Ambient conditions are moderate ($RH=45 \pm 5\%$ @ $T_{AMB}=25 \pm 2^{\circ}C$)



A bird's-eye view of the MAC test procedure (2/2)

(Status 15 January 2013)

- › Correction functions for a range of variables to improve stability of the results or to minimize test burden
 - › power correction (C_P)
 - › ambient conditions (C_{COP})
 - › cabin size (C_C) and glazing (F_{TTS})
 - › electric energy misbalance (P_{EL})

- › Feature check of MAC deactivation below 18°C


- › The MAC test results in the additional fuel consumption (ΔFC_{MAC}), caused by the operation of the MAC. Additionally, the additional CO₂ emission (ΔCO_{2MAC}) can be calculated.

Preliminary Results of the Round Robin




- › In general the procedure is found to be robust
- › Most sensitivities can be corrected for with correction functions
- › Some items are still open and need discussion or further investigation:
 - › Reproducibility (intra-lab variation) is not satisfying in some cases
 - › a preliminary solution is to increase the number of tests to 3 to improve statistical variance
 - › Family definition
 - › Small list of test details

Outlook on activities



- › Fine tuning of the procedure in close cooperation with the stakeholders
- › Further data analyses of the dataset to investigate the possible cause of intra-lab variation of some tests
- › Depending on the analyses possibly another small Round Robin to close remaining open issues
- › Iteration meetings to develop and complete the technical annex, starting 29th of January 2013

Interim results, minutes and presentations on Circabc



Thank you very much for your attention!

Do you have any questions?



Robin Vermeulen
robin.vermeulen@tno.nl
T +31 88 866 8424